6205 SYSTEM

USER HARDWARE MANUAL

0014877_REV_C

October 2014



EdgeTech
4 Little Brook Road
West Wareham, MA 02576

Tel: (508) 291-0057
Fax: (508) 291-2491
www.EdgeTech.com

The information, figures, and specifications in this manual are proprietary and are issued in strict confidence on condition that they not be copied, reprinted, or disclosed to a third party, either wholly or in part, without the prior, written consent of EdgeTech. Any reproduction of EdgeTech-supplied software or file sharing is strictly prohibited.

©Copyright 2014 by EdgeTech. All rights reserved.

Microsoft® and Windows® are registered trademarks of Microsoft Corporation.

Storm Case™ and Hardigg™ are trademarks of Pelican.

HYPACK® and HYSWEEP® are registered trademarks of Hypack, Inc.

ATTENTION – READ THIS FIRST!

All personnel involved with the installation, operation, or maintenance of the equipment described in this manual should read and understand the warnings and cautions provided below.

CAUTION!

This equipment contains devices that are extremely sensitive to static electricity. Therefore, extreme care should be taken when handling them. Normal handling precautions involve the use of anti-static protection materials and grounding straps for personnel.

WARNING!

High Voltage may be present in all parts of the system. Therefore, use caution when the electronics are removed from their containers for servicing.

CAUTION!

Operation with improper line voltage may cause serious damage to the equipment. Always ensure that the proper line voltage is used.

HARDWARE VARIATIONS AND COMPATIBILITY

The 6205 system contains both standard and proprietary hardware. At times, EdgeTech may change the standard components due to their availability or performance improvements. Although the component manufacturers—along with their models and styles—may change from unit to unit, replacement parts will generally be interchangeable.

EdgeTech will make every effort to see that replacement components are interchangeable and use the same software drivers (if applicable). At times, however, direct replacements may not exist. When this happens, EdgeTech will provide the necessary drivers with the replacement part, if applicable.

EdgeTech may also change certain hardware per customer requirements. Therefore, portions of this manual, such as parts lists and test features, are subject to change. These sections should be used for reference only. When changes are made that affect system operation, they will be explicitly noted. Also, some options and features may not be active in the customer's unit at time of delivery. Upgrades will be made available when these features are implemented.

Contact *EdgeTech Customer Service* with any questions relating to compatibility.

ABOUT THIS DOCUMENT

We, the employees at EdgeTech, would like to thank you for purchasing a 6205 system. At EdgeTech, it is our policy to provide high-quality, cost-effective products and support services that meet or exceed your requirements. We also strive to deliver them on-time, and to continuously look for ways to improve them. We take pride in the products we manufacture, and want you to be entirely satisfied with your equipment.

Purpose of this Manual

The purpose of this manual is to provide the user with information on the setup and use of EdgeTech's 6205 system. Although this manual encompasses the latest operational features of the 6205, some features may be periodically upgraded. Therefore, the information in this manual is subject to change and should be used for reference only.

Liability

EdgeTech has made every effort to document the 6205 system in this manual accurately and completely. However, EdgeTech assumes no liability for errors or for any damages that result from the use of this manual or the equipment it documents. EdgeTech reserves the right to upgrade features of this equipment, and to make changes to this manual, without notice at any time.

Warnings, Cautions, and Notes

Where applicable, warnings, cautions, and notes are provided in this manual as follows:

WARNING!

Identifies a potential hazard that could cause injury or death.

CAUTION!

Identifies a potential hazard that could damage equipment or data.

NOTE: *Recommendations or general information that is particular to the material being presented.*

WARRANTY STATEMENT

All equipment manufactured by EdgeTech is warranted against defective components and workmanship for a period of one year after shipment. Warranty repair will be done by EdgeTech free of charge.

Shipping costs are to be borne by the customer. Malfunction due to improper use is not covered in the warranty, and EdgeTech disclaims any liability for consequential damage resulting from defects in the performance of the equipment. No product is warranted as being fit for a particular purpose, and there is no warranty of merchantability. This warranty applies only if:

i. The items are used solely under the operating conditions and in the manner recommended in Seller's instruction manual, specifications, or other literature.

ii. The items have not been misused or abused in any manner, nor have repairs been attempted thereon without the approval of *EdgeTech Customer Service*.

iii. Written notice of the failure within the warranty period is forwarded to Seller and the directions received for properly identifying items returned under warranty are followed.

iv. The return notice authorizes Seller to examine and disassemble returned products to the extent Seller deems necessary to ascertain the cause for failure.

The warranties expressed herein are exclusive. There are no other warranties, either expressed or implied, beyond those set forth herein, and Seller does not assume any other obligation or liability in connection with the sale or use of said products. Any product or service repaired under this warranty shall be warranted for the remaining portion of the original warranty period only.

Equipment not manufactured by EdgeTech is supported only to the extent of the original manufacturer's warranties.

SOFTWARE SERVICE OVERVIEW

EdgeTech provides software services free of charge. This software agreement does not address customer-specified modifications or enhancements. These services may be ordered separately. Furthermore, EdgeTech software upgrades are meant for the sole use of EdgeTech customers. Any reproduction of EdgeTech-supplied software or file sharing is strictly prohibited.

Software Updates and Enhancements

EdgeTech customers can download new software releases with all modifications and enhancements from the EdgeTech FTP site. Major software issues, should they occur, will be reported directly to the customer. New software releases consist of the following:

- Software enhancements that are not on the price list
- Software fixes and changes
- Product integration
- Documentation updates to on-line help
- Tests for compatibility with other modules

Software patches consist of software that has undergone the following:

- Minor software enhancements
- Software fixes and changes
- Software Telephone, Facsimile, and E-mail Support

EdgeTech customers are entitled to contact *EdgeTech Customer Service* by telephone, facsimile, or e-mail to report a difficulty, discuss a problem, or to receive advice on the best way to perform a task. When contacted, *EdgeTech Customer Service* will do the following:

- Respond within 24 hours
- Immediately attend to serious problems affecting operations
- Attempt to find an immediate work-around

RETURNED MATERIAL AUTHORIZATION

Prior to returning any equipment to EdgeTech, a Returned Material Authorization (RMA) number must be obtained. The RMA will help us identify your equipment when it arrives at our receiving dock and track the equipment while it is at our facility. The material should be shipped to the address provided in the *EdgeTech Customer Service* section. Please refer to the RMA number on all documents and correspondences as well.

All returned materials must be shipped prepaid. Freight collect shipments will not be accepted. EdgeTech will pay freight charges on materials going back to the customer after they have been evaluated and/or repaired.

CAUTION!

If your product is a portable topside, never attempt to ship it in its Storm Case™ alone. Although rugged, these cases are not intended to be used as shipping containers, and the delicate internal components could be damaged if used in this manner.

The following steps apply only to material being returned from outside the Continental United States. Follow them carefully to prevent delays and additional costs.

1. All shipments must be accompanied by three copies of your proforma invoice, showing the value of the material and the reason for its return. If the reason is for repair, it must be clearly stated in order to move through customs quickly and without duties being charged. Whenever possible, please send copies of original export shipping documents with the consignment.
2. If the value of the equipment is over $1000, the following Shipper's oath must be sent with the invoice. This oath can be typed on the invoice, or on a separate letterhead:

"I, _____, declare that the articles herein specified are the growth, produce, or manufacture of the United States; that they were exported from the United States from the port of _____, on or about _____; that they are returned without having been advanced in value or improved in condition by any process of manufacture or any other means; and that no drawback, or allowance has been paid or admitted hereof."

Signed _____

3. If there is more than one item per consignment, a packing list must accompany the shipment. It is acceptable to combine the proforma invoice and packing list as long as the contents of each carton are clearly numbered and identified on the invoice.
4. Small items can be shipped prepaid directly to EdgeTech by FedEx, DHL, UPS, Airborne, etc.
5. If the equipment is the property of EdgeTech (formerly EG&G Marine Instruments Division), please insure for full value.
6. Fax one invoice, packing list, and a copy of the airway bill to EdgeTech upon shipment.

CUSTOMER SERVICE

Customer service personnel at EdgeTech are always eager to hear from users of our products. Your feedback is welcome, and is a valuable source of information that we use to continually improve these products. Therefore we encourage you to contact EdgeTech Customer Service to offer any suggestions or to request technical support:

E-mail:	service@edgetech.com
Mail:	4 Little Brook Road West Wareham, MA 02576
Telephone:	(508) 291-0057
Facsimile:	(508) 291-2491
24-Hour Emergency Technical Support Line:	(508) 942-8043

For more information please go to www.EdgeTech.com.

COMPANY BACKGROUND

EdgeTech (formerly EG&G Marine Instruments) traces its history in underwater data acquisition and processing back to 1966. EdgeTech has designed, developed, and manufactured products, instruments, and systems for the acquisition of underwater data—including marine, estuarine, and coastal applications—for over 45 years.

The company has responded to the needs of the scientific, Naval, and offshore communities by providing equipment—such as sub-bottom profilers, side scan sonar, acoustic releases, USBL positioning systems, and bathymetric systems—that have become standards in the industry.

EdgeTech has also consistently anticipated and responded to future needs through an active research and development program. Current efforts are focused on the application of cutting-edge CHIRP and acoustic technology.

TABLE OF CONTENTS

ATTENTION – READ THIS FIRST! iii
HARDWARE VARIATIONS AND COMPATIBILITY iv
ABOUT THIS DOCUMENT v
Purpose of this Manual v
Liability v
Warnings, Cautions, and Notes v
WARRANTY STATEMENT vi
SOFTWARE SERVICE OVERVIEW vii
Software Updates and Enhancements vii
RETURNED MATERIAL AUTHORIZATION viii
CUSTOMER SERVICE x
COMPANY BACKGROUND xi
TABLE OF CONTENTS xii
LIST OF FIGURES xv
LIST OF TABLES xvii
SECTION 1: OVERVIEW 1-1
1.1 Supplied Components 1-1
1.2 Optional Equipment 1-2
1.3 Software Description 1-2
SECTION 2: SYSTEM DESCRIPTION 2-1
2.1 The 6205 Sonar Head 2-1
2.1.1 Sonar Processor 2-2
2.1.2 Sonar Arrays 2-2
2.1.3 Sound Velocity Sensor 2-3
2.1.4 Housing 2-3
2.1.5 Mounting Plate 2-3
2.2 Field Exchangeable Frequency Operations 2-4
2.3 The 6205 Topside Interface 2-10
2.3.1 6205-R Rack Mount Topside Interface 2-11

2.3.2 6205-P Portable Topside Interface 2-12
2.3.3 Topside Computer Specifications 2-13
2.4 Deck Cable 2-14
2.5 Detailed Specifications 2-15
SECTION 3: CONNECTIONS AND FORMATS 3-1
3.1 Data Formats 3-1
3.2 System Connections and Data Flow 3-2
3.2.1 Ethernet LAN Connections 3-2
3.2.2 Serial Port Connections 3-3
3.2.3 Hardware Connectivity 3-3
3.2.3.1 Serial Port Configuration Examples 3-4
3.2.4 Sonar Data Flow 3-5
SECTION 4: INSTALLATION 4-1
4.1 Unpacking and Inspecting 4-1
4.2 Sonar Head Installation 4-1
4.2.1 Over-the-Bow Deployment 4-2
4.2.2 Over-the-Side Deployment 4-3
4.3 Positioning the Topside Interface Box 4-3
4.4 Topside Connections 4-4
4.5 Care and Maintenance 4-6
SECTION 5: PRINCIPLES OF OPERATION 5-1
5.1 Connecting to Sonar via Remote Desktop 5-1
5.1.1 Connecting with the 6205-R 5-1
5.1.2 Connecting with the 6205-P 5-2
5.2 Confirming Supporting Data is Present 5-3
5.3 Troubleshooting the SV Sensor 5-6
5.4 Activating 1PPS Time Sync Control 5-10
5.5 DISCOVER BATHYMETRIC 5-13
5.6 Third Party Software 5-13
5.6.1 HYPACK 5-13
5.6.2 SonarWiz 5-13

5.6.3 QINSy....5-14
5.6.4 CARIS....5-14
5.6.5 EIVA NaviSuite....5-14
SECTION 6: FAQ....6-1
APPENDIX A: BACKUP AND RESTORE....A-1
A.1 Backing up the System Drive....A-1
A.2 Restoring the System Drive....A-1
APPENDIX B: CONFIGURING COM PORTS....B-3
B.1 One Sensor....B-3
B.2 Two Sensors....B-10
B.3 Three Sensors....B-13
APPENDIX C: DRAWINGS AND DIAGRAMS....C-1

LIST OF FIGURES

Figure 2-1: 6205 Sonar Head Components 2-2
Figure 2-2: SVS in Nose of Sonar Head 2-3
Figure 2-3: Mounting Plate 2-4
Figure 2-4: Unit on Stable Platform 2-4
Figure 2-5: Removing the Cap Screws 2-5
Figure 2-6: Top Housing and Deck Cable Removed 2-5
Figure 2-7: Array Cables Unplugged 2-6
Figure 2-8: Cap Screws Removed 2-6
Figure 2-9: Port Array Removed 2-7
Figure 2-10: Cable in Keyway 2-7
Figure 2-11: Inserting New Array 2-8
Figure 2-12: Array Flush with Housing 2-9
Figure 2-13: Array Secured in Place 2-9
Figure 2-14: Array Replacement Complete 2-10
Figure 2-15: Rack Mount Topside with Real Time Connections 2-11
Figure 2-16: 6205-P Portable Topside 2-12
Figure 3-1: 6205-R Rack Mount Topside Interface Connections 3-3
Figure 3-2: Sonar Data Flow 3-6
Figure 4-1: 6205 Deployment, Option 1 – Over-the-Bow 4-2
Figure 4-2: 6205 Deployment, Option 2 – Over-the-Side 4-3
Figure 5-1: Manual Remote Desktop Credentials for Customer Supplied Computer 5-1
Figure 5-2: Sonar 192.9.0.101 Remote Desktop Connection Window 5-2
Figure 5-3: Sonar 192.9.0.101 Remote Desktop Connection Window 5-3
Figure 5-4: Serial Port Information Window 5-5
Figure 5-5: System Status Window 5-5
Figure 5-6: No Sound Velocity on Port 4 5-6
Figure 5-7: Sonar 192.9.0.101 Remote Desktop Connection Window 5-6
Figure 5-8: Closing the Sonar.exe Application 5-7
Figure 5-9: Connecting to COM4 using TeraTerm 5-8
Figure 5-10: COM4 Port Settings 5-8

Figure 5-11: Scrolling SV Data in Sonar.exe 5-9
Figure 5-12: Sonar 192.9.0.101 Remote Desktop Connection Window 5-10
Figure 5-13: Activating 1PPS Control in the Sonar.ini File 5-11
Figure 5-14: Incrementing Counts for 1PPS Signal 5-12
Figure 5-15: Sonar Alert for 1 PPS Error 5-12
Figure B-1: Sonar Remote Desktop Application, Main Screen B-4
Figure B-2: Sonar Remote Desktop, Shortcut to EdgeTech Folder B-5
Figure B-3: Finding the SonarSerial.ini File B-5
Figure B-4: SonarSerial.ini File B-6
Figure B-5: Diagnostic Window, Reporting Ports Inactive Error B-6
Figure B-6: Rebooting Sonar from the Main Screen B-7
Figure B-7: Checking Serial Port Information B-8
Figure B-8: Checking Sensor Status B-8
Figure B-9: Closing the System Status Window B-9
Figure B-10: SonarSerial.ini File B-10
Figure B-11: Checking Sensors' Usages B-12
Figure B-12: All Sensors Set B-13
Figure B-13: Checking all COM Ports B-15
Figure C-1: 6205 Sonar Head Drawing – A C-2
Figure C-2: 6205 Sonar Head Drawing – B C-3
Figure C-3: 6205 Sonar Head Drawing – C C-4
Figure C-4: 6205 Sonar Head Drawing – D C-5
Figure C-5: 6205 Wiring Diagram C-6
Figure C-6: 6205-P Portable Topside Interface Box C-7
Figure C-7: Array Color Codes C-8

LIST OF TABLES

Table 2-1: 6205 Topside Interface Specifications 2-15
Table 2-2: 6205 Sonar Head Specifications 2-16

SECTION 1: OVERVIEW

The EdgeTech 6205 is a combined, fully-integrated, swath bathymetry and dual frequency side scan sonar system. The 6205 uses multiple receive element transducers, and one discrete transmit element, to produce real-time high-resolution 3D maps of the seafloor, while also providing co-registered, simultaneous dual frequency side scan and bathymetric data. The high number of channels enables superb rejection of multi-path effects, reverberation, and acoustic noise.

The 6205 provides bathymetry and dual frequency side scan, operating at 230/550 kHz or 550/1600 kHz. Bathymetry data are obtained on either the 230 kHz or the 550 kHz frequency, while the Side Scan imagery is collected simultaneously on both frequencies. The sonar electronics and arrays are mounted onto a streamline body that is deployed over-the-bow or side of a survey vessel. Sonar data is transferred from the transceiver to the processing unit on board via an Ethernet network interface.

The standard configuration for the 6205 includes an integrated sound velocity sensor. The system can interface with standard DGPS/RTK systems, MRUs, SVPs, CTDs, Altimeters, and Gyros—altogether offering a powerful and versatile acquisition system that is suitable for many different applications.

1.1 Supplied Components

The following components come standard with the 6205 system:

- 6205 Swath Bathymetry and Side Scan Sonar Head with 20 m (65 ft) Deck Cable (please refer to the Cable Drawing in *APPENDIX C: DRAWINGS AND DIAGRAMS*).
- Sound Velocity Sensor (SVS, located in the Sonar Head)
- Large Pelican Hardigg™ Shipping Case
- 6205-R 19-inch Rack Mount Interface Box
- EdgeTech's DISCOVER BATHYMETRIC Acquisition Software
- Electronic Copy of the Manuals
- 6205 Tool Kit

> **NOTE:** *The customer is to provide the deck cable path between the 6205 Topside Interface Box and the 6205 Sonar Head.*

1.2 Optional Equipment

- Arrays for field exchangeable frequency operations
- 6205-P Portable Topside with Ruggedized Laptop preloaded with EdgeTech's DISCOVER BATHYMETRIC Acquisition Software
- Spares Kit

1.3 Software Description

EdgeTech's DISCOVER BATHYMETRIC Software Acquisition package provides a way to control, store, and display the bathymetry and dual frequency side scan sonar data. The data are presented on a color waterfall display and are stored in JSF format on the hard disk of the Topside Processor.

For more information on the DISCOVER BATHYMETRIC software, please refer to its manual (P/N 0014878).

SECTION 2: SYSTEM DESCRIPTION

The complete 6205 system consists of a Swath Bathymetry and Side Scan Sonar Head and a Topside Interface Box. This section describes the main components that make up the 6205 system and lists its specifications.

2.1 The 6205 Sonar Head

The 6205 Swath Bathymetry and Side Scan Sonar Head is available in a variety of frequency options:

- 230 kHz and 550 kHz with bathymetry on 230 kHz
- 230 kHz and 550 kHz with bathymetry on 550 kHz
- 550 kHz and 1600 kHz with bathymetry on 550 kHz

The frequency sets listed above were chosen to provide optimum results for any given water depth up to 200m (660 ft) below the transducer. The 230 kHz/550 kHz system with 230 kHz bathymetry was designed for water depths between 5m – 200m (15 ft – 660 ft), while the 550 kHz/1600 kHz for water depths between 0.5m – 50m (1.5 ft – 165 ft). The optimal frequency option depends on the survey requirements.

To mitigate the frequency tradeoffs, EdgeTech has designed the 6205 Sonar Head with field exchangeable arrays whereby the bathymetry frequency can be switched from the low frequency channel to the high frequency channel or vice versa. However, this feature only exists on the 230 kHz/550 kHz models.

Furthermore, the 6205 Swath Bathymetry and Side Scan Sonar Head comes standard with a Sonar Processor, Port and Starboard Sonar Arrays, a Sound Velocity Sensor (SVS), Housing (upper & lower), and a Mounting Plate. These components are demonstrated in *Figure 2-1*.



Figure 2-1: 6205 Sonar Head Components

> **NOTE:** *The terms used in Figure 2-1 will be referenced throughout the document.*

2.1.1 Sonar Processor

The 6205 Sonar Processor has a built in PC running Windows 7 Embedded as its operating system. The main firmware installed on the embedded PC is an application called Sonar.exe. This firmware controls the sonar's hardware and performs specific functions such as the signal processing and time synchronization of the acquired data.

2.1.2 Sonar Arrays

The 6205 provides bathymetry and simultaneous dual frequency side scan data and operates at 230/550 kHz or 550/1600 kHz. Bathymetry data are obtained on either the 230 kHz or the 550 kHz channel while the Side Scan imagery is collected simultaneously on both frequency channels. The 6205 utilizes two

arrays (port and starboard) to map the seafloor much like a dual head multibeam system. Each 6205 array is constructed using 11 independent longitudinal PZT elements. One of these is used for the transmit function and as a full resolution side scan receiver, while the remaining 10 elements make up an approximately half wavelength spaced array of sensors for its bathymetry receiver.

2.1.3 Sound Velocity Sensor

The 6205 Sonar Head has a flooded section that is used to house an AML Sound Velocity Sensor (SVS) providing a response time of 47 µs, a resolution of 0.001 m/s, and a theoretical accuracy of ±0.025 m/s. A closer look at the SVS is presented in *Figure 2-2*.



Figure 2-2: SVS in Nose of Sonar Head

2.1.4 Housing

The 6205 housing is composed of an upper and lower section made of Fiber Reinforced Polymer (FRP) composite and stainless steel. The housing supplies a streamline body for efficient underwater maneuvers rated up to 12 knots, while protecting the SVS, arrays, and deck cable connections.

2.1.5 Mounting Plate

The 6205 mounting plate is made of stainless steel and was designed with a variable bolt pattern to secure the system to several different deployment mechanisms, thereby cutting back on installation and mobilization time. The variable bolt pattern is illustrated on the following page in *Figure 2-3*. For a more detailed drawing, please refer to *Figure C-1: 6205 Sonar Head Drawing – A*.



Figure 2-3: Mounting Plate

2.2 Field Exchangeable Frequency Operations

In order to switch between the different bathymetry frequencies, the 6205 arrays must be exchanged with the corresponding bathymetry array. For instance, if the sonar head is currently configured as a 230 kHz/550 kHz Side Scan with 230 kHz bathymetry and the user wants to exchange the bathymetry frequency to the 550 kHz channel, then the following procedure should be followed. The only tool needed for this operation is a $^{3}/_{16}$" inch Allen wrench.

1. Place the unit on a stable and level platform, such as a workbench or boat deck.

Figure 2-4: Unit on Stable Platform

2. Take off the top half of the housing by removing the fourteen $^{1}/_{4}$" – 20 x $^{5}/_{8}$" cap screws using a $^{3}/_{16}$" Allen key.



Figure 2-5: Removing the Cap Screws

3. Unplug the deck cable (green) from the bottle, remove it from the top housing, and set the top housing and deck cable aside.

Figure 2-6: Top Housing and Deck Cable Removed

4. Unplug the port and starboard array cables (yellow and black cables) from the bottle. Please don't unplug the SVS cable.



Figure 2-7: Array Cables Unplugged

5. Tilt the lower housing onto its starboard side and remove all six $^{1}/_{4}$" – 20 x 1.5" cap screws using the same $^{3}/_{16}$" Allen key.



Figure 2-8: Cap Screws Removed

6. Remove the port array from the lower housing by pushing on the fore section of the array so that it is titled away at an angle from the housing.

Figure 2-9: Port Array Removed

7. Then push on the aft section of the array and pull forward so that the cables come through the keyway. Remove the entire array from the housing.

Figure 2-10: Cable in Keyway

8. Take the new port array and thread it through the keyway, pushing the aft end into the groove.



Figure 2-11: Inserting New Array

CAUTION!

Each array is labeled according to which side it corresponds to so please ensure the port array is installed on the port side and the starboard array is installed on the starboard side. The sonar processor contains calibration data that is specific to each array and these must be installed correctly in order for calibration to be successful.

9. Then push back and tilt the array into place until the array face is flush with the housing.



Figure 2-12: Array Flush with Housing

10. Secure it in place using the six $^{1}/_{4}$" – 20 x 1.5" cap screws and the $^{3}/_{16}$" Allen key.



Figure 2-13: Array Secured in Place

11. Tilt the housing on its port side and repeat steps 5 – 10 to replace the starboard array with the alternate one.

12. Connect the array cables to the bottle, making sure the correct pins match up.
13. Thread the deck cable through the hole in the top housing and reconnect it to the bottle.
14. Replace the top housing, ensuring that the deck cable is in the aft position of the sonar head. Securing it with the fourteen $^{1}/_{4}$" – 20 x $^{5}/_{8}$" cap screws and $^{3}/_{16}$" Allen key.



Figure 2-14: Array Replacement Complete

2.3 The 6205 Topside Interface

The 6205 Topside Interface has two purposes:

- To provide power to the Sonar Head
  AND
- To provide a direct link between the Sonar Head, any supporting sensors, and the Topside Computer.

The sonar interface box delivers power to the system and transmits/receives data via the provided 20 m (65 ft) Deck Cable and a SubConn 16 pin wet mate connector. The topside sonar interface box also supplies three RS232 serial ports to intake navigation, heading, and attitude data from the supporting sensors and an Ethernet port to communicate with the topside computer.

The first two RS232 serial ports are configured for high speed and high accuracy, while the third RS232 serial port is configured for standard serial connections. Typical latencies for the high speed/high accuracy ports are less than 100us, whereas the standard serial port may have up to 100ms.

This topside interface box comes in two forms:

- Rack mountable topside interface box for use with a customer-supplied computer
  OR
- Portable splash proof interface box that includes a ruggedized laptop

These two options are defined in the following sub-sections.

2.3.1 6205-R Rack Mount Topside Interface

The 6205-R Rack Mount Topside Interface box was designed to slide into a 19-in Rack Mount Optima Case. It provides three input/output serial ports, four Ethernet ports, AC power input, on/off switch, and two BNC connectors that supply an input trigger and 1PPS sync. The three input serial ports act as a dry connection to the sonar head for all ancillary information (i.e. position, attitude, time, etc.), while the four Ethernet ports provide 100Mbps connection from the sonar head to the topside computer. These interfaces are illustrated in *Figure 2-15*.

Figure 2-15: Rack Mount Topside with Real Time Connections

The Rack Mount interface option does not come with a topside computer and must be supplied by the customer. Please see the minimum requirements provided in sub-section *2.3.3*). EdgeTech's DISCOVER BATHYMETRIC Acquisition Software is included on a DVD that is supplied upon delivery of the 6205 Sonar Head. This software can also be downloaded from the EdgeTech FTP site. Please contact *EdgeTech Customer Service* for FTP site credentials.

2.3.2 6205-P Portable Topside Interface

The 6205-P Portable Topside Interface is a splash proof design of the 6205-R Rack Mount Interface box. It offers all the same connections to the 6205 Sonar Head for the supporting sensors (i.e. GPS, MRU, etc.) through a series of break out cables. See *Figure 2-16* for a picture of the portable option.

Figure 2-16: 6205-P Portable Topside

This option comes standard with a ruggedized laptop, preloaded with EdgeTech's DISCOVER BATHYMETRIC Acquisition Software. The ruggedized laptop is a high performance PC, running Windows 7 Professional as its operating system. It also has a Dual Quad Core processor (8 cores), and comes with a 500 GB hard drive. This laptop is used to simultaneously execute EdgeTech's DISCOVER BATHYMETRIC Acquisition Software, as well as any third party data acquisition and post processing software.

CAUTION!

The laptop's performance changes when running on battery power so please ensure the laptop is plugged in when operating the sonar and acquiring real time bathymetry and side scan data.

2.3.3 Topside Computer Specifications

The topside computer must be able to run EdgeTech's DISCOVER BATHYMETRIC Acquisition Software and any additional third party software. In order to do so, it must include the following minimum requirements.

- Windows 7 Professional Operating System
- Quad-Core Intel Core i7-4900MQ @ 2.8GHz Processor or similar
- 8 GB of Memory (RAM)
- 500GB Hard Drive
- 3 USB Ports
- 1 Ethernet Port
- 1 GB Graphics Card

The 6205-P includes its own ruggedized laptop preloaded with EdgeTech's DISCOVER BATHYMETRIC Acquisition Software and all supporting software. The laptop ships to the customer with the specifications listed below.

- Windows 7 Professional Operating System 64 bit
- Quad-Core Intel Core i7-4900MQ @ 2.8GHz Processor
- 8 GB of Memory (RAM)
- 500GB Hard Drive
- Intel HD Graphics 4600 Card
- NVIDIA GeForce GT 850M (2GB DDR3)
- Super-Multi DVD-RW Drive
- 2 USB 2.0 Ports
- 2 USB 3.0 Ports
- Intel Single Band Wireless-N 7260 with Bluetooth
- 1 Ethernet RJ45 Port
- 1 VGA Port
- 1 HDMI Port

NOTE: *Even though the topside laptop computer included with the 6205-P may look and operate like a general purpose PC it is not recommended to install additional software other than the provided EdgeTech and Bathymetric Third Party Package (a list of the approved third party packages is provided in Section 5.6). Installing other software besides the ones supplied with the system can have undesirable effects, such as poor and/or slow performance when acquiring bathymetry and dual frequency side scan data.*

2.4 Deck Cable

The deck cable is a 20 meter (65 feet) underwater, high speed network data and power cable. The deck cable includes Cat 5e 4 pair stranded conductors that meets or exceeds TIA 568-B, and is suitable for 10Base-T and 100Base-T. The deck cable is also terminated with a Subconn 16 pin wet mate connector on both ends, has a breaking strength of 545 kg (1200 lbs), and provides power and telemetry to the 6205 Sonar Head.

NOTE: *This deck cable is not to be used for towing.*

2.5 Detailed Specifications

Detailed specifications for the 6205 Topside Interfaces and Sonar Heads are provided in *Table 2-1* and *Table 2-2*.

INTERFACE MODEL	6205 – RACK MOUNT	6205 - PORTABLE
PHYSICALS		
Size	48.3 L x 52.1 W x 8.9 H cm (19 L x 20.5 W x 3.5 H in)	49.5 L x 38.1 W x 19.1 H cm (19.5 L x 15 W x 7.5 H in)
Weight	5.4 kg (12 lbs)	13.6 kg (30 lbs)
Construction	Aluminum	Polyethylene/Polyurethane
Interfaces	1 x 1 PPS via BNC 1 x Trigger Out via BNC 4 x 100 BaseT Ethernet Ports 3 x Serial RS-232 Ports	1 x 1 PPS via BNC 1 x Trigger Out via BNC 3 x 100 BaseT Ethernet Ports 3 x Serial RS-232 Ports
POWER REQUIREMENTS		
Input Power Supply	115/230 VAC Auto-Sensing	115/230 VAC Auto-Sensing
Output Power Supply	60VDC	48VDC

Table 2-1: 6205 Topside Interface Specifications

SONAR HEAD MODEL	230/550 KHZ SS – 230/550 BATHY	550/1600 SS - 550 KHZ BATHY
PHYSICALS		
Size	76.2 L x 21.1 W x 27.9 H cm (30 L x 8.3 W x 11 H in)	76.2 L x 21.1 W x 27.9 H cm (30 L x 8.3 W x 11 H in)
Weight	19.9 kg (43.9 lbs)	19.9 kg (43.9 lbs)
Construction	FRP Composite / Stainless Steel Reinforced	FRP Composite / Stainless Steel Reinforced
Color	Blue Angels Yellow	Blue Angels Yellow
Sealing	O-Ring Seal with Purge Valve	O-Ring Seal with Purge Valve

SONAR HEAD MODEL	230/550 KHZ SS – 230/550 BATHY	550/1600 SS - 550 KHZ BATHY
SIDE SCAN SONAR		
Center Frequency	230/520 kHz	520/1610 kHz
Range (per Side)	225/125 m (738/410 ft)	125/35m (410/115 ft)
Range Resolution	30/15 mm (1.18/0.4 in)	15/6 mm (0.4/0.2 in)
Beam Width Along Track	0.64°/0.47° (2-way)	0.47°/0.2° (2-way)
Depression Angle	30°	30°
SWATH BATHYMETRY		
Center Frequency	230 kHz/520kHz	520 kHz
Maximum Swath	350 m (1148 ft)	150 m (492 ft)
Beam Width Along Track	0.64°/0.47°	0.47°
Ping Repetition Rate (Both Sides Simultaneously)	15 m (16 ft) = 50 Hz 25 m (82 ft) = 30 Hz 50 m (164 ft) =15Hz 100 m (328 ft) = 8 Hz 200 m (656 ft) = 4 Hz	5 m (16 ft) = 150 Hz 25 m (82 ft) = 30 Hz 50 m (164 ft) = 15 Hz 100 m (328 ft) = 8 Hz 150 m (492 ft) = 5 Hz
Max Depth Below Transducers	215 m (705 ft)	90 m (295 ft)
POWER REQUIREMENTS		
DC Input Range	36-60 VDC (48 VDC Nominal)	36-60 VDC (48 VDC Nominal)
Max In Rush Current	3.5A	2.5A
ENVIRONMENT		
Operating Temperature	0°C to 40°C (32°F to 104°F)	0°C to 40°C (32°F to 104°F)
Storage Temperature	-20°C to 60°C (-4°F to 140°F)	-20°C to 60°C (-4°F to 140°F)
Relative Humidity	Operating 0 to 80%, Non-Operating 0 to 100%	Operating 0 to 80%, Non-Operating 0 to 100%
Max Depth Below Transducers	215 m (705 ft)	90 m (295 ft)

Table 2-2: 6205 Sonar Head Specifications

SECTION 3: CONNECTIONS AND FORMATS

The 6205 System relies on specific data formats and connections to produce its high-quality images and measurements. This section describes these data formats and connections along with providing diagrams to help the user better understand the hardware and data flow within the system.

3.1 Data Formats

In order to collect valid survey data the following is required to support the survey operations and correct processing of the 6205 Bathymetry and Dual Frequency Side Scan echo data:

a. GPS Position in NMEA format, latitude and longitude; minimum of 5Hz
b. Heading data in NMEA format or EM1000 binary format; minimum of 20Hz
c. Attitude or Roll, Pitch, and Heave data in TSS1 or EM1000 binary format; minimum of 20Hz
d. Time sync data in NMEA format; minimum of 1Hz

These data may be supplied by 1, 2, or 3 individual sources, and are listed below in order of priority.

a. Position Data – this may be supplied via any of the following NMEA type sentences/messages:
    i. $xxGGA
    ii. $xxGLL
    iii. $xxRMC
    iv. $xxGGK ** (Applanix PosMV Format)
    v. $PTNL, GGK, … ** (Trimble Format)

    ** = Non-NMEA standard sentences

b. Heading Data – this may be input via:
    i. NMEA, $xxHDT sentence, OR
    ii. EM1000 binary format along with attitude data

c. Attitude (Roll, Pitch, and Heave) Data – this may be input via:
    i. TSS1 format, OR
    ii. EM1000 binary format

d. Time Input - supported sentences are in order of priority/use
    i. $xxZDA
    ii. $xxRMC
    iii. $xxGGK (derived from data in item a. above)
    iv. $xxGGA (only supports time, no date field)
    v. $xxGLL (only supports time, no date field)

NOTE 1: *the prefix "$xx" represents the proprietary NMEA message prefix for a specific manufacturer. $GPGGA, $GPZDA, etc. are example NMEA output sentences for a Hemisphere GPS.*

NOTE 2: *We recommend that you also supply the system with a source of Speed Over Ground in NMEA format (i.e. VTG, minimum of 1Hz) so that the system can correctly compute the Along Track Distance between each ping and display it in the DISCOVER BATHYMETRIC Software.*

3.2 System Connections and Data Flow

The following sub-sections describe the connections and data flow for the 6205 system.

3.2.1 Ethernet LAN Connections

The Ethernet LAN connection from the Sonar Head to the 6205 Topside Interface is made using a physical wired connection via the standard 20 m (65 ft) deck cable. This cable is connected to the Sonar Head via a 16 pin SubConn wet mate connector and provides a direct connection from the Sonar Head to the 6205 Sonar Interface box. The 6205 Sonar Interface then connects to a Topside Computer via a standard RJ-45 Ethernet plug. The correct IP addresses for the sonar head and topside PC are listed below.

- Sonar Head IP Address = 192.9.0.101
- Topside PC IP Address = 192.9.0.99

NOTE: *The factory defaults for the 6205 sonar head IP address is 192.9.0.101 and should not be changed for any reason. The ruggedized laptop that is supplied with the 6205-P portable topside interface will also be preconfigured to 192.9.0.99 on delivery from the factory. It is only when the customer has to supply their own topside computer that the IP address needs to be set to the address above.*

3.2.2 Serial Port Connections

There are three RS-232 serial ports provided on the 6205 Sonar Interface box. COM1 and COM2 have been configured for high speed and high accuracy). COM3 is configured for standard RS-232 serial connections. Typical latencies for the high speed/high accuracy ports are less than 100us, whereas the standard serial port has up to 100ms.

These serial ports are provided to intake the navigation, heading, and attitude (roll, pitch, and heave) data from the supporting sensors. Please see *APPENDIX B: CONFIGURING COM PORTS* on how to configure the COM ports.

3.2.3 Hardware Connectivity

Figure 3-1 is a block diagram that illustrates the interconnections between the 6205 Swath Bathymetry and Dual Frequency Side Scan Sonar Head, the 6205-R Rack Mount Topside Interface, and all supporting sensors. This illustration also gives three examples of possible sensor configurations that are explained below.



Figure 3-1: 6205-R Rack Mount Topside Interface Connections

The 6205-P Portable Topside Interface connections are similar and are presented in *APPENDIX C: DRAWINGS AND DIAGRAMS*.

In *Figure 3-1*, the 6205 Sonar Interface connects to the Sonar Head via the Deck Cable. Time, navigation, heading, roll, pitch, and heave data from the supporting sensors via COM ports 1, 2, and/or 3, are inputted at the Sonar Interface, passed through the Deck Cable, and logged by the Sonar Processor in the Sonar Head.

These data are transmitted (along with the raw side scan data) with a common timestamp up the Deck Cable to the 6205 Sonar Interface, and are then passed to the Topside Computer through an Ethernet cable and via the 100Mbps link on Ethernet Port 1 (IP Address: 192.9.0.99).

The Topside Computer then processes these data using the DISCOVER BATHYMETRIC software to send amplitude, angle and range data to the 3rd party software for logging and post processing. This process is explained in further details in the following section. The 3rd party software and DISCOVER BATHYMETRIC processors may all run on the same computer.

3.2.3.1 Serial Port Configuration Examples

The first example in *Figure 3-1* depicts a sensor interfacing to the 6205 Sonar Interface that provides time, navigation (latitude/longitude), heading, roll, pitch, and heave data over one serial connection—such as a NovaTel ProPak 6 or Applanix PosMV. As depicted by *Figure 3-1*, the sensor is connected to COM1.

The second example shows the most common interfacing scenario, a GPS that provides navigation and heading data, accompanied by a motion sensor for attitude measurements. The COM ports should be assigned as such:

- COM1 = MRU (Roll, Pitch, Heave)
- COM2 = GPS (Navigation and Heading)

These assignments may be interchanged between COM1 and COM2 because both ports have been configured for high speed and high accuracy. COM3 should not be used in this scenario.

The third and last example portrays a situation where the GPS does not provide heading data. In this case, three sensors are required: a GPS for navigation (latitude/longitude), a Gyro for heading, and a motion sensor for roll, pitch, and heave measurements. Therefore, all three COM ports should be used and assigned as follows:

- COM1 = MRU (Roll, Pitch, Heave)
- COM2 = Gyro (Heading)
- COM3 = GPS (latitude/longitude/time)

The sensors allocated to COM1 and COM2 may be interchanged for the same reason stated above in the second example. The GPS data, or latitude and longitude data, must be allotted to COM3 because

position can tolerate a 100ms latency, whereas attitude and heading are crucial to correcting the wide swath of data.

> **NOTE:** *To configure the serial ports according to the examples given above, please see APPENDIX B: CONFIGURING COM PORTS.*

3.2.4 Sonar Data Flow

The DISCOVER BATHYMETRIC software acquisition package provides a way to control, store, and display the bathymetry and side scan sonar data. DISCOVER BATHYMETRIC contains two processors: one to process the bathymetry solutions, called the Bathymetric Processor, and the second to process and display the dual frequency side scan data. To illustrate the data flow between DISCOVER, the Bathymetric Processor, and any third party software, the block diagram in *Figure 3-2* is used.

> **NOTE:** *The 6205 Sonar Interface Box in the flow chart below can be either the 6205-R Rack Mount Interface Box or the 6205-P Portable Interface Box.*


Time, Heading, Position, and Motion Data
[1] 6205 Sonar Interface Box
[2] Auxiliary Data Sent to Sonar Head
6205 Sonar Head
[3] Sonar Data plus Auxiliary Data get Time Stamped, Packaged with SV, and Sent Back to Interface Box.
SV
[4] DISCOVER BATHYMETRIC
[7] Third Party Software
[6] Range/Angle Data + Auxiliary Data + Dual Frequency SS Data
Raw Sonar Data
Range/Angle Data
[5] Bathymetric Processor
[8] Third Party Files

Figure 3-2: Sonar Data Flow

The flow chart in *Figure 3-2* demonstrates the following:

1. The auxiliary sensors provide time, heading, position (latitude/longitude), and motion (roll, pitch, and heave) data to the 6205 Sonar Interface Box via the provided RS-232 serial ports.
2. These auxiliary data are then relayed to the 6205 Sonar Head via the Deck Cable.
3. Here, the auxiliary data are combined with the raw sonar data and instantaneous sound velocity (SV) measurements, where they are time stamped with a common value, and then sent back to the 6205 Sonar Interface.
4. DISCOVER BATHYMETRIC Acquisition Software takes in the raw sonar data and sends it to the Bathymetric Processor.
5. The Bathymetric Processor processes the raw sonar data to produce uncorrected range and angle data, and then transmits this back to DISCOVER BATHYMETRIC, where it is packaged with the auxiliary and dual frequency side scan data. At this point, each ping is represented by a complete data package containing all sonar and auxiliary data.

NOTE: *Once the data is passed back to DISCOVER BATHYMETRIC these data are shown on the provided graphical displays to illustrate the bathymetry and simultaneous dual frequency side scan data in real time. These data may also be recorded as a *.JSF file if the user desires.*

6. This complete data package (range/angle, dual frequency side scan, and all auxiliary data) is sent to the third party software.
7. The third-party software then logs these complete data packets to their native format. The third-party software also provides graphical displays to show the bathymetry, dual frequency side scan, and auxiliary data.
8. Finally, these three-dimensional third party data files contain every piece of information to post process the data and generate hydrographic final products.

SECTION 4: INSTALLATION

This section provides an overview for unpacking, inspecting, installing, and caring for the EdgeTech 6205 Swath Bathymetry and Dual Frequency Side Scan Sonar System.

4.1 Unpacking and Inspecting

The Sonar Head and Interface Box with cables, optional Laptop, and CDs are all shipped in two, reusable, heavy duty transport case. All documentation, including the manuals, is provided in electronic form on the CDs.

Before unpacking the system's components, inspect the shipping containers for any damage. If any damage is noticed, please report it to the carrier and to EdgeTech immediately. If the shipping containers appear damage free, carefully unpack the components and inspect them.

Also, please check the packing list and verify that all the items on the list are included. Again, if any damage is found, please report it to the carrier and to EdgeTech immediately. If any items are missing, please contact *EdgeTech Customer Service*. Do not install or operate any equipment that appears to be damaged.

Although the items shipped may vary, depending on the customer's requirements, the standard components for the 6205 Swath Bathymetry and Dual Frequency Side Scan Sonar system are listed in *SECTION 1: OVERVIEW*.

4.2 Sonar Head Installation

The 6205 system's installation on the survey vessel is the customer's responsibility, and certain considerations need to be kept in mind. The Sonar Head can be mounted on the side of a vessel, but it is recommended to secure the 6205 to the bow of the boat. If the customer wishes to mount the sonar off the side of their vessel, care must be taken to ensure keel clearance.

4.2.1 Over-the-Bow Deployment

The first, and recommended option, is to mount the 6205 Sonar Head to the bow of the survey vessel. An example of an over-the-bow deployment is depicted in the photographs in *Figure 4-1*. If help is needed with this type of installation, please do not hesitate to contact *EdgeTech Customer Service*.

Figure 4-1: 6205 Deployment, Option 1 – Over-the-Bow

4.2.2 Over-the-Side Deployment

An alternative to the bow mount is to secure the 6205 Sonar Head over the side of the survey vessel via a pole. An example of an over-the-side deployment is illustrated in the images in *Figure 4-2*. If help is needed with this type of installation, please contact *EdgeTech Customer Service*.

Figure 4-2: 6205 Deployment, Option 2 – Over-the-Side

4.3 Positioning the Topside Interface Box

The Topside Interface Box can be set up several ways, depending on the model purchased. The 6205-R 19-in Rack Mount version should be located and set up in a dry, sheltered area on the survey vessel that is protected from weather and water spray.

The 6205-P portable design is a bit more versatile since it is watertight when closed (but cannot ever be submerged) and can be set up anywhere on the survey vessel that is most convenient. Care should be taken however, to keep the ends of the breakout cables dry.

Avoid areas of direct sunlight, especially in tropical environments, as heat build-up can occur and viewing status indicators can become difficult. The temperature should also consistently be between 0°C and 40°C (32°F and 104°F). Furthermore, the location should enable direct communications with the deck crew that is operating the survey vessel, Sonar Head, and other supporting sensors.

4.4 Topside Connections

After the Sonar Head has been installed, and the Topside Interface Box correctly placed on the survey vessel, the supporting sensors can now be connected. To connect the supporting sensors, Sonar Head, and Topside Interface Box:

1. Setup the MRU as described in the MRU's user manual.
2. Position and secure the MRU to the vessel's center of motion. If the MRU cannot be mounted in this location, then please try to mount it as close as possible to the center of motion.
3. Setup the GPS as described in the GPS's user manual.
4. Position and secure the GPS Antennas so that they have a clear view of the sky. Also ensure that the GPS receiver is secured in a dry, sheltered area on the survey vessel that is protected from weather and water spray.
5. Ensure the sonar head is installed properly on the pole mount (whether it is at the bow or side of the vessel).
6. Measure the relative location of the MRU to the vessel's center of motion. If the MRU was mounted exactly at the vessel's center of motion, these measurements would be recorded as (0,0,0).
7. Measure the location of the GPS relative to the vessel's center of motion. Typically, the primary antenna is used as the source of position. In this case, use the location of the primary antenna to measure the installation offset for the GPS.

> **NOTE:** *These measurements are important and will be used later as installation offsets in the third party software. Please make sure to measure and note the exact location of the sensors to the vessel's center of motion. Also, please remember the Z dimension is referenced to the water line.*

8. Measure the location of the sonar head's acoustic center relative to the vessel's center of motion. The location of the acoustic center is provided in the Sonar Head drawing in *APPENDIX C: DRAWINGS AND DIAGRAMS*.
9. Provide power to the 6205 Interface Box via the provided power cable.
10. Connect the Sonar Head to the 6205 Topside Interface box via the Subconn 16 pin connector.
11. Connect the MRU to COM1 and the Dual Head GPS to COM2 (or vice versa).

a. A MRU is used to measure the pitch, roll, and heave of the survey vessel.

b. A dual head GPS is used to gather heading and position (latitude/longitude) data.

> **NOTE:** *If the GPS does not supply heading (i.e. single head only), then a Gyro (or other source of heading) must be used. In the case where another sensor is needed to provide heading, the sensors should be connected as COM1 – MRU, COM2 – Heading, COM 3 – GPS. The low latency ports (COM1 and COM2) must be designated to the low latency sensor information (i.e., attitude and heading).*
>
> **NOTE:** *Please refer to sub-section 3.2.2 for more information on connecting the COM Ports. Also, please use* ***APPENDIX B****: CONFIGURING COM PORTS to configure the COM ports for the individual sensors.*

12. Connect the 6205 Interface box to the topside computer using an Ethernet cable.
13. Turn the PC on and launch DISCOVER BATHYMETRIC Software.
14. If desired, launch any one of the supported third party software packages (e.g., Hypack, SonarWiz, or QINSy), setup the 6205 drivers, and input the installation offsets measured in steps 6 through 8.

At this point, all equipment and software is ready for surveying. See *SECTION 5: PRINCIPLES OF OPERATION* for use of the system.

4.5 Care and Maintenance

The 6205 Sonar Head is not designed for long-term deployments, and it is not recommended to keep the system in water for more than two weeks at a time. After each mission, the system should be rinsed thoroughly with freshwater, making sure to rinse the SVS at the front and connectors at the back using the carry slots located on the sonar housing.

The faces of the arrays should also be inspected after each deployment for organism growth or damage. If any residue is noticed, clean the array faces using a wash cloth with mild soap and water. If any damage is observed, contact *EdgeTech Customer Service* immediately.

CAUTION!

Never turn the 6205 Sonar Head on and run in air. Damage to the transducers can occur.

SECTION 5: PRINCIPLES OF OPERATION

This section describes how to connect to the sonar, ensure all supporting data is present within the system for proper operation, and correctly time sync the 6205 data. It also briefly describes the EdgeTech DISCOVER BATHYMETRIC software and provides a list of the compatible third party topside interfaces. A complete guide to EdgeTech's DISCOVER BATHYMETRIC software can be found in the Software User Manual (P/N 0014878).

5.1 Connecting to Sonar via Remote Desktop

There are two ways to connect to the 6205 Sonar depending on which interface box is connected. These procedures are listed below.

5.1.1 Connecting with the 6205-R

If using a customer-supplied computer with the 6205-R (Rack Mount) Interface Box:

1. Navigate to the **Remote Desktop** application by clicking on the Windows Start button > All Programs > Accessories > Remote Desktop Connection. Alternatively, click on the Windows Start button, type **mstsc** in the search box, and hit <Enter>. The following window will appear:



Figure 5-1: Manual Remote Desktop Credentials for Customer Supplied Computer

2. Connect to the 6205 Sonar using an IP address of **192.9.0.101** and User name of **Administrator**.

3. When prompted for a password, input ***admin***.

   Once logged on, the following window will appear:


Sonar - 192.9.0.101 - Remote Desktop Connection
74.1 Sonar : Alerts 10 SER
File Recording Transmit Misc
[Self Test: OK] [Sonar: OFF OFF] [2205_SS_SSLBATHY10] [OF:1]
20SP: OFF
20SS: OFF
21SP: OFF
21SS: OFF
Shortcut to EdgeTech
CPUID HWMonitor

Figure 5-2: Sonar 192.9.0.101 Remote Desktop Connection Window

This window represents the main firmware running on the embedded CPU located in the bottle of the Sonar Head. Called *Sonar.exe*, this program is responsible for controlling the sonar's hardware and performs specific functions such as the signal processing and time synchronization of the acquired data.

5.1.2 Connecting with the 6205-P

If using the supplied laptop with the 6205-P (Portable Topside) Interface Box:

1. Launch the **Remote Desktop to Sonar** application on the desktop screen. If prompted for a password, input ***admin***.

   Once logged on, the Sonar Application will be displayed on the screen (as in *Figure 5-2*). This window represents the main firmware running on the embedded CPU located in the bottle of the Sonar Head. Called *Sonar.exe*, this program is responsible for controlling the sonar's hardware and performs specific functions, such as the signal processing and time synchronization of the acquired data.

5.2 Confirming Supporting Data is Present

To ensure the Sonar Head's processing unit is communicating properly with the Topside Processor, follow these steps:

> **NOTE:** *This section assumes all auxiliary sensors have been connected to the 6205 Interface Box (whether this is the 6205-R or 6205-P) the Sonar Head is installed on the survey vessel and is submerged in seawater.*

1. On the Desktop, launch **Remote Desktop to Sonar**. The following window should appear:


Sonar - 192.9.0.101 - Remote Desktop Connection
74.1 Sonar : Alerts 10 SER
File Recording Transmit Misc
[Self Test: OK] [Sonar: OFF OFF] [2205_SS_SSLBATHY10] [OF:1]
20SP: OFF
20SS: OFF
21SP: OFF
21SS: OFF
EdgeTech
HWMonitor

Figure 5-3: Sonar 192.9.0.101 Remote Desktop Connection Window

2. Click on Menu > Misc > Serial Port Information.
3. Check each COM port in the drop down menu to ensure the correct baud rates are set and data is coming through for each device and in the correct format (*Figure 5-4*).
    a. COM1 = MRU
    b. COM2 = GPS
    c. COM4 = Sound Velocity Sensor located in the Sonar Head's housing

> **NOTE:** *The GPS and MRU are interchangeable on COM1 and COM2 as long as the appropriate baud rate is set in the drop down menu next to the channel assignment in the Serial Port Information Window (Figure 5-4, red arrow).*
>
> *More information on how to configure the COM ports is presented in APPENDIX B: CONFIGURING COM PORTS.*

If all systems are working properly, close this window and proceed to Step 4. If there is an issue with one of the ports, please contact *EdgeTech Customer Service*.

> **CAUTION!**
>
> *Sound velocity is extremely important for the system to operate correctly. If sound velocity measurements are not present (i.e., port is reporting no data), use sub-section 5.3 Troubleshooting the SV Sensor to go through the troubleshooting process.*

4. Click on Menu > **File** > **Show Status**. The System Status window will appear.
5. On the bottom of the window, click on the **Config** bullet and then on the drop down menu named **Config Item**.
6. Select **Serial** from the list.
7. Check to make sure all sensors' usage percentages are well below 80% as shown in *Figure 5-5*. If they are not, increase the baud rates of the sensors until these percentages drop. Make sure to change the baud rate accordingly in **Sonar**.
8. When satisfied with the incoming data, press **OK** in the System Status window, and then close the **Sonar - 192.9.0.101 - Remote Desktop Connection** window.



Figure 5-4: Serial Port Information Window


System Status
** Serial1 ** On Com1001, Queues:N., State OK, ParseErrors 3
Msgs: Recvd 0 Generated 4528 RecvQOF 0 XQOF 0
Bytes:(Out 0 In 122535) Last(Out 0 In 297[1..324])
Capacity 23.43% ASCII: :000000 -0000U-0
3a 30 30 30 30 30 30 20 2d 30 30 30 30 55 2d 30
** Serial2 ** On Com1002, Queues:N., State OK, ParseErrors 3
Msgs: Recvd 0 Generated 4528 RecvQOF 0 XQOF 0
Bytes:(Out 0 In 122535) Last(Out 0 In 297[1..324])
Capacity 53.23% NMEA
3a 30 30 30 30 30 30 20 2d 30 30 30 30 55 2d 30
** Serial4 ** On Com4, Queues:N., State OK, ParseErrors 0
Msgs: Recvd 0 Generated 4528 RecvQOF 0 XQOF 0
Bytes:(Out 0 In 122535) Last(Out 0 In 297[1..324])
Capacity 1.23% ASCII: 1545.23 II
30 30 30 30 2e 30 30 30 20 0d 0a
Save Above List to SonarList.txt
Config Item
Serial
Config
Messages
Log
POST
Diag
Pause
Cmd
Clear Statistics

Figure 5-5: System Status Window

5.3 Troubleshooting the SV Sensor

In some cases the sound velocity sensor may not boot properly. If this occurs, DISCOVER BATHYMETRIC will show a **Port 4: Error** on its **Diagnostic Window** indicating that no sound velocity measurements are being reported to the sonar head. An example of this error is shown in *Figure 5-6*.

Figure 5-6: No Sound Velocity on Port 4

If this error persists longer than 30 seconds, follow the procedure below in order to resolve the issue:

1. Place the sonar head in water so that the bottom half of the shell is submerged. This will submerge the sound velocity sensor as well.
2. On the Desktop, launch **Remote Desktop to Sonar**. The following window should appear:


Sonar - 192.9.0.101 - Remote Desktop Connection
74.1 Sonar : Alerts 10 SER
File Recording Transmit Misc
[Self Test: OK] [Sonar: OFF OFF] [2205_SS_SSLBATHY10] [OF:1]
20SP: OFF
20SS: OFF
21SP: OFF
21SS: OFF
EdgeTech
HWMonitor

Figure 5-7: Sonar 192.9.0.101 Remote Desktop Connection Window

3. Click on Menu > Misc > Serial Port Information.

4. Check **Chan 4 on Com 4** from the drop down list to see if there is any data being reported by the port.
5. If no data is present, cycle the power on the sonar head using the On/Off switch on the interface box. Please allow the sonar to be off for at least 10 seconds before turning it back on.
6. Once the sonar is reconnected, go back into the **Remote Desktop** application and check **Chan 4 on COM 4** again as in step 4 above.
7. If data is reported by the port, then proceed to normal operation. If not, continue to step 8.
8. Close out of *Sonar.exe* by clicking on the '**X**' in the top right corner (designated by the red arrow in *Figure 5-8*).


Sonar - 192.9.0.101 - Remote Desktop Connection
74.1 Sonar : Alerts 10 SER
File Recording Transmit Misc
(Self Test: OK) (Sonar: OFF OFF) (2205_SS_SSLBATHY10) (OF:1)
20SP: OFF
20SS: OFF
21SP: OFF
21SS: OFF
Shortcut to EdgeTech
CPUID HWMonitor

Figure 5-8: Closing the Sonar.exe Application

9. Double click the "Shortcut to EdgeTech" icon, then navigate to the Utilities/Teraterm folder, and launch the **ttermpro.exe** program.
10. Select **Serial**, choose **COM4** from the drop down menu (*Figure 5-9*), and click **OK**.
11. Now, choose **Setup** from the top menu and then **Serial port…**
12. Configure the serial port options as shown in *Figure 5-10* and click **OK**.



Figure 5-9: Connecting to COM4 using TeraTerm



Figure 5-10: COM4 Port Settings

13. Input the following commands:

    Hit <Enter> to start communications to SV sensor.
    Type in “SET STARTUP NOHEADER” and <Enter>.
    Type in “SET STARTUP MONITOR” and <Enter>.
    Type in “SV FORMAT 42” and <Enter>.
    Type in “SV ZEROSUPPRESSION 0 seconds” and <Enter>.
    Type in “SET SAMPLE 1/S” and <Enter>.
    Type in “SET DETECT 06” and <Enter>.
    Type in “SET RXOFF” and <Enter>.

> **NOTE:** *The “SET RXOFF” command disables the Rx line to the SV sensor. If a connection needs to be reestablished, please press and hold <Enter> for 3-5 seconds until >>> is displayed on the screen. Proceed to enter commands as normal.*

14. Cycle the power on the Sonar Head using the On/Off switch on the interface box. Please allow the sonar to be off for at least 10 seconds before turning it back on.

15. Reconnect to the sonar via the Remote Desktop application and check COM4 using the Sonar application as before in steps 3 and 4 above. SV data should not be scrolling as in:



Figure 5-11: Scrolling SV Data in Sonar.exe

16. If SV data is still not present, please contact *EdgeTech Customer Service* using the provided information on page xi of this manual.

5.4 Activating 1PPS Time Sync Control

To activate the 1PPS Time Sync Control for the 6205 System the following procedure must be performed:

> **NOTE:** *This section assumes the 1PPS signal has been connected to the 6205 Interface Box (whether this is the 6205-R or 6205-P) via a BNC connector and the Sonar Head is submerged in seawater.*

> **CAUTION!**
>
> *Never turn the 6205 Sonar Head on and run in air. Damage to the transducers can occur.*

1. Connect to the 6205 Sonar via the Remote Desktop Application as laid out in sub-section *5.1*.
2. Exit out of the **Sonar.exe** application by clicking on the **X** in the top right hand corner (*Figure 5-12*, indicated by the red arrow).


Sonar - 192.9.0.101 - Remote Desktop Connection
74.1 Sonar : Alerts 10 SER
File Recording Transmit Misc
[Self Test: OK] [Sonar: OFF OFF] [2205_SS_SSLBATHY10] [OF:1]
20SP: OFF
20SS: OFF
21SP: OFF
21SS: OFF
Shortcut to EdgeTech
CPUID HWMonitor

Figure 5-12: Sonar 192.9.0.101 Remote Desktop Connection Window

3. Click on the **Shortcut to EdgeTech** folder located on the desktop and navigate to EdgeTech\SSSSonarBathy\Sonar folder.
4. Find the **sonar.ini** file and open it using the Notepad application.
5. Scroll to the bottom of the file and find the section labeled **Options for SAIBU Card**.

6. Delete the semicolon in front of the keyword **TimeSyncMask=4** so that the file looks identical to *Figure 5-13*.



Figure 5-13: Activating 1PPS Control in the Sonar.ini File

7. Save the file and exit.

> **CAUTION!**
>
> *Ensure that no other field in this file is changed. This could lead to an improper configuration within the Sonar Application!*

8. Navigate back to the yellow desktop window and click on the shortcut labeled **Sonar.exe**. The **Sonar.exe** application will reboot with the newly applied configuration to accept 1PPS time sync.

9. To ensure the 6205 System is using the new configuration, click on the **File** menu, and then **Show Status**. If the 1PPS is connected to the 6205 Interface Box via a BNC connector, then the **PPS: #** field should be incrementing as it receives the signal (*Figure 5-14*, circled in red).

   If it is not incrementing, make sure the BNC is properly connected to the 1PPS function on the 6205 Interface Box. The Sonar application will also complain of a 1PPS error as indicated by the red arrow in *Figure 5-15*.

> **NOTE:** *Alerts 2 NET may appear in the Sonar application if the 6205 System is not connected to the DISCOVER BATHYMETRIC Acquisition Software and this alert may safely be disregarded at this time.*


74.1 Sonar : Alerts 2 NET
File Recording Transmit Misc
[Self Test: OK] [Sonar: OFF OFF] [2205_SS_SSLBATHY10] [OF:0]
20SP: OFF
20SS: OFF
21SP: OFF
21SS: OFF
System Status
** Low Rate IO ***********
0 0 0 0 0 0 0 0
** Status ***************** POST 0 TimeStat f0 SerStat 0 0
Activity 0 OfCount 0 FreeDsk 36357799 DiskFlags=0
MsgErrors Total=0 LastErrors=0 0 0 0 0 0 0 0 0 0
Temp(Air=0:0 Bot=0) Power48 0 Override 1
Xmit Protect State 0 (NOT LIMITED) ReasonForProtection:N/A
Per Subsystem: 0.000(0%) 0.000(0%) 0.000(0%) PSI 0%
** Time Sync ************** 08/06/2014 14:51:19:0942
Src: 222(0 0) SrcChanged 0 Sources 5 Ratios(RTC0.99986 CPU1.00000)
PPS: #9 Errs 0(ErrMS 0 0..0 Del 0) Interval 0.0000 Inhibits 0
RTC: (ErrMS -9 -9...-1) CPUTimeSets 0
NET: Del#0 (CurMS 0 0.. 0) Gets 0 Sets 0(Last 0) Ignd 0
DSP: #0(ErrMS 0 Min 0 Max 0 Period 0 Min 0 Max 0) 0.0%
** Overflow Counters ******
DSP=(Q:0,D:0) => PCIQ=0 => DataQ=0 => FFT=0 => FinalQ=0
Other Internal Counters: StartUp=0 DSPResets=0 DataWindow=0
Queue Depth in KB : Network 0, Disk 0, Playback 0
** Main *****************
NetCmd Disconnected NetData Disconnected PNS: 0
DSP #0 Last Read KB 0 Max Read KB 0
Save Above List to SonarList.txt
Config Item Summary Config Messages Log POST Diag Pause
Cmd
Clear Statistics

Figure 5-14: Incrementing Counts for 1PPS Signal


74.1 Sonar : Alerts 82 NET PPS
File Recording Transmit Misc
[Self Test: OK] [Sonar: OFF OFF] [2205_SS_SSLBATHY10] [OF:0]
20SP: OFF
20SS: OFF
21SP: OFF
21SS: OFF

Figure 5-15: Sonar Alert for 1 PPS Error

10. Close the Remote Desktop Application, launch the DISCOVER BATHYMETRIC Acquisition Software, and proceed with normal operations.

5.5 DISCOVER BATHYMETRIC

EdgeTech's **DISCOVER BATHYMETRIC** Acquisition package provides a way to control, store, and display bathymetric and dual-frequency side scan sonar data. These data are presented on a color waterfall display and stored in the binary EdgeTech JSF file format on the hard disk of the Topside Processor. The JSF file format has been in use for 10+ years and has new public extensions to support the additional bathymetry data messages.

Please refer to the **DISCOVER BATHYMETRIC Acquisition Software Manual** for a full description of its feature and functions (EdgeTech P/N 0014878).

5.6 Third Party Software

Currently, there are several third party software packages that have been approved by EdgeTech to use with the 6205 system, and work continues to expand the number of available topsides. A brief description is listed below. For the latest list of third party topsides, please contact *EdgeTech Customer Service*.

5.6.1 HYPACK

The processed bathymetry and side scan data is sent in real-time to the HYPACK®/HYSWEEP® survey applications. These applications display and record the bathymetric data in HYPACK's HSX format. These HSX files can then be used off line in the MBMax, Side Scan Mosaic, and other proprietary packages that support these formats to edit, clean, and mosaic the collected data.

For more information on Hypack, please visit http://www.hypack.com/new/.

5.6.2 SonarWiz

SonarWiz from Chesapeake Technologies Inc. is an all-in-one suite of programs for the real-time acquisition of sonar data. The latest version of SonarWiz, called SonarWiz 5, now offers a bathymetry module to acquire and post process the real time 6205 Swath Bathymetry and Dual Frequency Side Scan data. The latest release also has the ability to ingest the native EdgeTech JSF files post survey in order to post process the sonar data files recorded by DISCOVER BATHYMETRIC.

For more information on SonarWiz, please visit http://www.chesapeaketech.com/products/sonarWiz-5.php.

5.6.3 QINSy

QINSy is a hydrographic data acquisition, navigation, and processing software package. The suite of applications can be used for various types of surveys, ranging from simple single beam surveys up to complex offshore construction works.

For more information on QINSy, please visit their website at: http://www.qps.nl/display/qinsy/main.

5.6.4 CARIS

CARIS HIPS and SIPS is a comprehensive bathymetric, seafloor imagery, and water column data-processing software. The HIPS and SIPS software enables the user to simultaneously process multibeam, backscatter, side scan sonar, LiDAR, and single beam data. With its latest importer, released in July 2014, it now supports EdgeTech's bathymetry and side scan data formats.

For more information on CARIS, please visit their website at: http://www.caris.com/.

5.6.5 EIVA NaviSuite

EIVA's NaviSuite constitutes a complete, advanced, multipurpose suite of software products for virtually any subsea sonar and sensor survey or engineering operation. From online data acquisition to offline post-processing, NaviSuite covers the entire data workflow in a continuous, non-sequential process.

For more information on EIVA and its products, please visit their website at:
http://www.eiva.com/products/software.

SECTION 6: FAQ

This section provides a list of frequently asked questions pertaining to the EdgeTech 6205 Swath Bathymetry and Dual Frequency Side Scan System.

1. **Which frequency is better? The 230 kHz or the 550 kHz?**

   Both systems work very well, but each has its own benefits depending on the environment, water depth, and application. For customers who mainly operate in open ocean environments with a depth of 10 to 200 meters (32 to 656 ft) of water, the 230 kHz system is the optimal solution. For customer's surveying mostly in channels, creeks, and other enclosed bodies of water and operating in depths of about 0.5 to 50 meters (1.5 to 165 ft), the 550 kHz system is the best fit. Please contact *EdgeTech Customer Service* for more information on the benefits of each system.

2. **Does the 6205 system interface with Ethernet devices?**

   Currently the 6205 system can only interface with supporting sensors via the three COM ports (RS-232) on the back of the Topside Interface Box. Please check with *EdgeTech Customer Service*, as it is an upcoming feature.

3. **Where is the best place to mount the 6205 Sonar Head on the survey vessel?**

   The bow of a survey vessel is always the best place to mount the 6205 Sonar Head. By placing the system at the bow, the sonar should be far enough away from most interference, such as hull echoes, propeller noise, wake, etc.

4. **How long can I keep my 6205 Sonar Head in the water for?**

   The 6205 system was not designed with a permanent submerged installation in mind. It is recommended that the 6205 system remain submerged for no longer than 2 weeks at a time, especially in warm, salty waters. Fouling and corrosion may degrade the measurements of the 6205 system and/or the sound velocity sensor in the nose of the Sonar Head.

   It is recommended that the array faces be checked regularly, and if fouling is observed, to clean them using a wash cloth with mild soap and fresh water. It is also recommended that the SVS in the nose be regularly inspected and cleaned, as well as calibrated once every two years.

5. **How often should I rinse my system?**

   Rinse the 6205 Sonar Head after every mission. Please pay special attention to the SVS sitting in the bottom portion of the housing, and the connectors towards the back of the housing, rinsing them thoroughly using the rinse holes provided.

6. **What if the 6205-R Rack Mount Topside Interface Box does not turn on?**

   If the 6205-R Rack Mount Topside Interface Box does not turn on, please check the on/off switch on the back panel. It is located next to the power plug.

7. **Do I always need a sound velocity cast?**

   It is always a good idea to collect a sound velocity profile, especially in the area where the user collected his or her patch test data. Most likely the water being operated in does not have a uniform sound velocity, and depending on how drastic the profile is, a depth error as large as 1.6 m has been observed.

8. **Can I incorporate RTK Tide measurements with the 6205 system?**

   Yes. Most third party software packages have the ability to set up a device driver to acquire these data. A 1PPS sync is needed in this case, as these measurements are typically manipulated offline. Please see sub-section *5.2: Confirming Supporting Data is Present*.

9. **Why can't I feed navigation directly into the Topside Computer?**

   In order for the 6205 to properly process the bathymetry data, it needs all of the auxiliary data, such as time, position, heading, roll, pitch, and heave. By inputting the supporting device directly into the computer poses a risk of mismatching time stamps. If the time stamps do not match, the bathymetric processor will not know which ping to coordinate the auxiliary data with.

10. **How often should I connect to the Remote Desktop Connection (Sonar.exe) and check to see the status of the supporting data?**

    The user should only need to do this if a device is not connected properly. If this is the case, DISCOVER BATHYMETRIC will display its diagnostic window and show which serial port is causing the error. Usually going in to the Remote Desktop application is done during training with an experienced representative from EdgeTech present. Except as outlined in this manual, it is not recommended for users to connect to the sonar without EdgeTech support.

11. **What do I do if I do not see data scrolling in DISCOVER BATHYMETRIC?**

    Check to see if the Sonar Head has connected to DISCOVER BATHYMETRIC by checking the status of the network (NET: ON) down in the right hand corner of the DISCOVER main window (please see the DISCOVER BATHYMETRIC Acquisition Software Manual for more information). It usually takes about a minute and a half for the Sonar Head to boot and connect to the Topside Processor. If the problem persists, please contact *EdgeTech Customer Service*.

12. **What do I do if the Diagnostic window will not disappear, even after I've clicked Done?**

    If DISCOVER BATHYMETRIC is connected, check the Diagnostic window for any missing data on any of the three/four COM ports (depending on how the particular system has been configured). If one Port is showing "Port Inactive", check the connection of the device and the Topside Interface Box. If a Port is showing "Unknown Data", first check to make sure the baud rate matches the sonar's baud rate as in sub-section *5.1 Connecting to Sonar via Remote Desktop*. If this matches, then please check the format of the devices output data. Ensure the data format follows sub-section *3.1* of this manual). If the problem persists, please contact *EdgeTech Customer Service*.

13. **Can the 6205 acquire dual frequency side scan at the same time as the bathymetry data?**

    The 6205 can log all three data sets simultaneously to the same data file (i.e., bathymetry, low frequency side scan, and high frequency side scan) in real-time.

14. **Can the 6205 System measure pilings or vertical objects?**

    The 6205 system can measure vertical objects, if configured to do so. By default, the system is set to record and bin the interferometric data using a specified number of horizontal bins. To map vertical objects, please change the binning mode to Angle Binning. Please see the DISCOVER BATHYMETRIC Manual for further instructions.

15. **What do I do if I do not see data scrolling in my Third Party Software?**

    Check to see if DISCOVER is connected to the third-party software using the Connections Information window (or more information, please refer to the DISCOVER BATHYMETRIC Acquisition Software manual). Also, ensure all ancillary data is coming through DISCOVER and across to the third party software. In most cases, the ancillary information is needed before the third party software can plot soundings on their real-time display.

16. **Which third party software packages interface with the 6205 Swath Bathymetry and Dual Frequency Side Scan System?**

    EdgeTech has approved a small number of Third Party Topsides for acquisition and processing of the bathymetry and side scan data. Currently, Hypack, SonarWiz, QINSy, and EIVA software packages have been approved, but work continues to expand the number of topsides. CARIS HIPS/SIPS also supports our native JSF files for post processing. Please contact *EdgeTech Customer Service* for updates.

17. **What should I do if my portable topside (i.e. 6205 ruggedized laptop) crashes?**

    Please refer to APPENDIX *A: BACKUP AND RESTORE* for instructions on how to restore the portable topside. If the user experiences any issues, please contact *EdgeTech Customer Service* immediately so we can help restore the system and get the survey back up and running as soon as possible.

APPENDIX A: BACKUP AND RESTORE

The following appendix outlines the procedures for backing up and restoring the system drive.

A.1 Backing up the System Drive

To back up the system drive:

18. Insert image disk into USB slot and boot the computer.
19. To enter setup, press F2 for laptops or Del for rack-mount systems.
20. Go to Boot and change HDD BBS Priorities.
21. Highlight option 1 and change to Image Disk.
22. Confirm Boot Option Priorities are set to DVD, then Image Disk.
23. Save and Exit.

    Paragon software will load…
24. Click Cancel under Confirm Network (if applicable).
25. Select Post-mortem Backup, and then click Next.
26. Ensure all check boxes below are checked (First hard disk track & Master book record & OS Part (C:)
27. Click Next, and then select save data to local/network drives.
28. Click Next, and then select Recovery Media OR Group # PC# (if reusing a flash drive).
29. Name archive group, product, and s/n. Then click next.
30. Insert the date for the comment (e.g., 2/23/2013). Then click next.
31. You have now successfully backed up the system.

A.2 Restoring the System Drive

1. Insert the Image Disk into USB slot and boot computer.
2. Press F2 for laptops and Del for rack-mount systems.
3. Go to Boot and change HDD BBS Priorities.
4. Highlight option one and change to Image Disk

5. Confirm Boot Option Priorities are set to DVD, then Image Disk.
6. Save and Exit.

   Paragon software will load…
7. Click Cancel under Confirm Network (if applicable).
8. Click Post-mortem Restore.
9. Select Recovery Media, and Product and s/n.
10. Click Next.
11. Select Basic MBR Hard Disk number and click Next.
12. Select the drive to restore the archive to and click Next.
13. Do not select any options and click Next.
14. Click Yes, Apply these Changes Physically.
15. Click Next.
16. After the restore is complete, reboot the PC and right click on Computer>Properties.

If you have internet access, do the following:

17. Set the direct LAN connection to automatic and connect ETHERNET cable.
18. Click the Change Windows Key
19. Type the correct ID.
20. Activate this ID and affix sticker to the rear of the computer.
21. Reset the direct LAN connection to 192.9.0.99.
22. Set the wireless connection to 192.9.0.100, and rename it, removing the wireless number.
23. Rename the computer to product type-xxxxx.

If you do not have Internet access, call 888-725-1047. This is the direct number to Windows 7 Professional Activation help.

APPENDIX B: CONFIGURING COM PORTS

There are three available COM ports on the Interface Box to provide the necessary information to the 6205. This information includes position (latitude/longitude), heading, attitude (roll, pitch, and heave), and time. This appendix explains how to configure the three COM ports depending on what type of sensors are used.

B.1 One Sensor

One sensor, such as the Applanix PosMV, may be used to supply position (latitude/longitude), heading, attitude, and a time source. For this type of configuration, only COM1 will be utilized.

To configure the COM ports for one sensor:

1. Turn on the Topside PC and connect the 6205 via the deck cable to the 6205 Topside Interface Box.
2. Turn on the 6205 Sonar Head and run the Remote Desktop Application, named Sonar. The main screen as in *Figure B-1* should appear.

   Here, the user will see the Sonar Application running (designated by the blue arrow). This is the firmware that controls the system.
3. Click on the 'X' at the top right to close the firmware.
4. Now, double click on the Shortcut to EdgeTech icon (red arrow, *Figure B-2*) and open the SSSonarBathy folder, then the Sonar folder.
5. Look for the SonarSerial.ini file (*Figure B-3*) and open it using WordPad or Notepad (*Figure B-4*).
6. Under [Serial2] and [Serial3] set Create = 0, select File > Save, and close the file.

CAUTION!

Do not alter the file in any way other than what has been specified.

This will deactivate COM ports 2 and 3. By deactivating these ports, Sonar will report to DISCOVER that only one sensor is to be used on COM1 to parse the necessary sensor information. Therefore, DISCOVER will not throw up any errors if a sensor is not connected to COM2 or COM3.

If steps 3 through 6 were not carried out, then these errors would be reported in the Diagnostic window (*Figure B-5*).

7. Close the SonarSerial.ini file and reboot the Sonar Firmware by double clicking on the Sonar icon in the main Sonar Remote Desktop Screen (designated by the green arrow in *Figure B-6*).

   Proceed to Step 8.



Figure B-1: Sonar Remote Desktop Application, Main Screen



Figure B-2: Sonar Remote Desktop, Shortcut to EdgeTech Folder


EdgeTech in Towfish ▸ EdgeTech ▸ SSSSonar ▸ Sonar
Search Sonar
Organize
Open
Print
Burn
New folder
Desktop
Downloads
EdgeTech (EdgeT
Recent Places
ETN (EdgeTech N
ETS (EdgeTech Sc
MH (EdgeTech N
Libraries
Documents
Music
Pictures
Videos
Computer
OS (C:)
Name
Date modified
Type
Size
sonar.ini 7/15/2011 4:03 PM Configuration sett... 3 KB
Sonar.opt 1/17/2012 8:46 PM OPT File 1 KB
SONAR.TXT 4/14/2011 1:11 PM Text Document 37 KB
sonar_230_SP_JT.ini 7/21/2011 1:06 PM Configuration sett... 3 KB
sonar_540_SP.ini 7/15/2011 4:03 PM Configuration sett... 3 KB
sonar18.8.exe 10/20/2010 8:16 AM Application 1,096 KB
SonarArrayInfo.ini 1/17/2012 9:01 PM Configuration sett... 2 KB
SonarArrayInfo.txt 6/16/2011 3:15 PM Text Document 2 KB
SonarObsoleteKeywords.txt 9/14/2010 1:02 PM Text Document 18 KB
SonarSerial.ini 6/21/2011 11:59 AM Configuration sett... 1 KB
SonarSerial.Txt 6/30/2011 4:36 PM Text Document 29 KB
SonarSerialFormats.txt 1/4/2010 10:42 AM Text Document 1 KB
SonarXDucer.txt 1/4/2010 10:42 AM Text Document 2 KB
SoundConnect.txt 2/25/2005 1:00 AM Text Document 1 KB
SoundNoConnect.txt 12/10/2007 7:07 PM Text Document 1 KB

Figure B-3: Finding the SonarSerial.ini File

SonarSerial.ini - Notepad

File Edit Format View Help

```
[Serial1]
; Set for GPS or MRU (TSS1 sentence + ORE Sentence + Std NMEA)
Create=1
Parser=4  ;Must be 4
Port=1001
;Baud=9600
Baud=38400


[Serial2]
; Set for TSS (TSS1 sentence + ORE Sentence + Std NMEA)
Create=1
Parser=4
Port=1002
Baud=115200    ;115200 for ORE MRU or 38400 bit for the SMC
Disk=1
VerifyChecksum=0


[Serial3]
; Spare Port, change create to 1 to use
Create=1
Parser=4
Port=3
;Baud=9600
Baud=9600
;wetportchecksum = 100

[Serial4]   ;Dont touch ever or there will be no Sound Velocity data
; Com4 set for Valeport MiniSVS
; Setup: Using the vendor provided configuration utility, set the following:
;   Baud:            19200
Create=1
Parser=9
Port=4
Baud=19200
```

Figure B-4: SonarSerial.ini File



Figure B-5: Diagnostic Window, Reporting Ports Inactive Error



Figure B-6: Rebooting Sonar from the Main Screen

8. Now, plug the device into COM 1.
9. Click on the **Misc.** at the top of the Sonar screen (as shown in *Figure B-7*), then **Serial Port Information.**
10. Check COM1 and set the correct baud rate for that device by using the drop down menu shown in blue (*Figure B-7*). When the correct baud rate is set, the State should say **OK** and **Errors** should not be increasing (as circled in green, *Figure B-7*). The correct data string should also be scrolling in the lower part of the window (green arrow, *Figure B-7*).
11. Now click on **File** > **Show Status** in the sonar window (circled in red, *Figure B-8*).
12. On the right hand side of the window, click on the **Config** bullet under the Update button and then on the drop down menu named **Config Item** (in green).
13. Select **Serial** and then click on the **Update** button several times (blue arrow).
14. Check to make sure the sensor's usage percentage is well below 80% (circled in purple). If it is not, increase the baud rate of the sensor, change the baud rate under Serial Port Information as done before in step 10, and check the Status again. Otherwise, the sonar will report errors. Proceed to step 15.



Figure B-7: Checking Serial Port Information



Figure B-8: Checking Sensor Status

15. When satisfied with the incoming data, press OK in the System Status window (*Figure B-9*).



Figure B-9: Closing the System Status Window

16. Finally, close the Sonar - 192.9.0.101 - Remote Desktop Connection window.

> **NOTE:** *If this window is left open during data acquisition, the user may experience a very slow computer. This is because the remote desktop application uses a large amount of the link capacity to stay open. So it is always a good idea to close the remote desktop application when finished with the configurations.*

B.2 Two Sensors

Two sensors, such as a dual-headed GPS (heading, position, and time source) and a Motion Reference Unit (roll, pitch, and heave) may be used to supply the necessary information. For this type of configuration, only COM1 and COM2 will be used.

To configure the COM ports for the two sensors:

1. Follow steps 1 through 6 as stated previously under appendix sub-section *B.1*.
2. Under [Serial3] set Create = 0, select File > Save, and close the file (Figure *B-10*).

CAUTION!

Do not touch anything else or the system's configuration files could be seriously compromised and functionality may suffer.



Figure B-10: SonarSerial.ini File

This will deactivate COM3. By deactivating this port, Sonar will report to DISCOVER that only two sensors are to be used on COM1 and COM 2 to parse the necessary sensor information. Therefore, DISCOVER will not throw up any errors if a sensor is not connected to COM3.

3. Reboot the Sonar Firmware by double clicking on the Sonar icon in the main Sonar Remote Desktop Screen (designated by the green arrow in *Figure B-6*).
4. Now, plug in the devices into COM 1 and COM 2. Which device is connected to which COM port does not matter, as long as their respective ports and baud rates are set in Sonar.
5. Click on the **Misc.** at the top of the Sonar screen (as shown in *Figure B-7*), then **Serial Port Information.**
6. Check COM1 and set the correct baud rate for that device by using the drop down menu shown in blue (*Figure B-7*). When the correct baud rate is set, the State should say **OK** and **Errors** should not be increasing (as circled in green, *Figure B-7*). The correct data string should also be scrolling in the lower part of the window (green arrow, *Figure B-7*).
7. Now Check COM2 and set the correct baud rate for the other device as done before in Step 6.
8. Now click on **File** > **Show Status** in the sonar window (circled in red, *Figure B-11*).
9. On the right hand side of the window, click on the **Config** bullet under the **Update** button and then on the drop down menu named **Config Item** (in green, *Figure B-11*).
10. Select **Serial** and then click on the **Update** button several times (blue arrow, *Figure B-11*).
11. Check to make sure the sensors' usage percentages are well below 80% (circled in purple, *Figure B-11*). If they are not, increase the baud rate of the sensor, change the baud rate under **Serial Port Information** as done before in steps 6 and 7, and check the **Status** again. Otherwise the sonar will report errors.



Figure B-11: Checking Sensors' Usages

12. When satisfied with the incoming data, press **OK** in the System Status window (*Figure B-11*).
13. Finally, close the Sonar - 192.9.0.101 - Remote Desktop Connection window.

> **NOTE:** *If this window is left open during data acquisition, the user may experience a very slow computer. This is because the remote desktop application uses a large amount of the link capacity to stay open. So it is always a good idea to close the remote desktop application when finished with the configurations.*

B.3 Three Sensors

Three sensors, such as a gyro (heading), a GPS (position, and time source), and a Motion Reference Unit (roll, pitch, and heave) may be used to supply the necessary information. For this type of configuration, all available COM ports will be used.

To configure the COM ports for the three sensors, the following steps should be carried out.

1. Follow steps (1.) through (6.) as stated previously under appendix sub-section *B.1*.
2. Make sure Create=1 under each [Serial#]. (*Figure B-12*)



Figure B-12: All Sensors Set

3. Then select File > Save, and close the file.

CAUTION!

Do not touch anything else or the system's configuration files could be seriously compromised and functionality may suffer.

4. Close the SonarSerial.ini file and reboot the Sonar Firmware by double clicking on the Sonar icon in the main Sonar Remote Desktop Screen (designated by the green arrow in *Figure B-6*).
5. Now, plug in the devices into COM 1, COM 2, and COM 3. The Gyro should be connected to COM1, the MRU COM2, and the GPS to COM3. The devices connected to COM1 or COM2 may be interchanged but the GPS must be connected to COM3.
6. Click on the **Misc.** at the top of the Sonar screen (as shown in *Figure B-7*), then **Serial Port Information.**
7. Check COM1 and set the correct baud rate for that device by using the drop down menu shown in blue (*Figure B-7*). When the correct baud rate is set, the **State** should say **OK** and **Errors** should not be increasing (as circled in green, *Figure B-7*). The correct data string should also be scrolling in the lower part of the window (green arrow, *Figure B-7*).
8. Now check COM2 and set the correct baud rate for the other device as done before in Step 6.
9. Also, remember to check COM3 as before and set the correct baud rate for GPS.
10. Now click on **File** > **Show Status** in the sonar window (circled in red, *Figure B-8*).
11. On the right hand side of the window, click on the **Config** bullet under the **Update** button, and then on the drop down menu named **Config Item** (in green, *Figure B-8*).
12. Select Serial and then click on the Update button several times (blue arrow, *Figure B-13*).
13. Check to make sure the sensors' usage percentages are well below 80% (circled in purple, *Figure B-13*). If they are not, increase the baud rate of the sensor, change the baud rate under Serial Port Information as done before in steps 6 and 7, and check the Status again, otherwise the sonar will report errors.
14. When satisfied with the incoming data, press **OK** in the System Status window (*Figure B-13*).
15. Finally, close the Sonar - 192.9.0.101 - Remote Desktop Connection window.

NOTE: *If this window is left open during data acquisition, the user may experience a very slow computer. This is because the remote desktop application uses a large amount of the link capacity to stay open. So it is always a good idea to close the remote desktop application when finished with the configurations.*


Sonar - 192.9.0.101 - Remote Desktop Connection
19.2 Sonar
File Recording Transmit Misc
System Status
** Serial1 ** On Com1001, Queues:N., State OK, ParseErrors 3
Msgs: Recvd 0 Generated 4528 RecvQOF 0 XQOF 0
Capacity 3.43% NMEA
** Serial2 ** On Com1002, Queues:N., State OK, ParseErrors 3
Msgs: Recvd 0 Generated 4528 RecvQOF 0 XQOF 0
Capacity 23.43% ASCII: :000000 0000U-0
** Serial3 ** On Com3, Queues:N., State OK, ParseErrors 0
Msgs: Recvd 0 Generated 4528 RecvQOF 0 XQOF 0
Capacity 53.23% NMEA
** Serial4 ** On Com4, Queues:N., State OK, ParseErrors 0
Msgs: Recvd 0 Generated 4528 RecvQOF 0 XQOF 0
Capacity 1.23% ASCII: 1545.23 ||
OK
Update
Config
Errors
POST
Diag
Config Item
Serial
Refresh
Save List
Clear Ctrs
Cmd
Start
19.2 Sonar
2:48 PM
Recycle Bin

Figure B-13: Checking all COM Ports

APPENDIX C: DRAWINGS AND DIAGRAMS

This appendix contains the following supporting drawings for the 6205 Swath Bathymetry and Dual Frequency Side Scan Sonar System:

- 6205 Sonar Head Drawing Parts A through D
- 6205 Deck Cable Wiring Diagram
- 6205-P Portable Topside Interface Box Diagram
- 6205 Array Color Codes Diagram

> **NOTE:** *Sonar Head Drawing Parts A through D reference a single drawing, part number 0013735 Rev A. The drawing was segmented for this manual to allow for easier viewing.*



Figure C-1: 6205 Sonar Head Drawing – A



Figure C-2: 6205 Sonar Head Drawing – B



Figure C-3: 6205 Sonar Head Drawing – C



Figure C-4: 6205 Sonar Head Drawing – D


UNLESS AS MAY BE OTHERWISE PROVIDED BY CONTRACT, THESE DRAWINGS AND SPECIFICATIONS ARE THE PROPERTY OF "EDGETECH" AND ARE ISSUED IN STRICT CONFIDENCE AND SHALL NOT BE REPRODUCED, COPIED OR USED AS THE BASIS FOR THE MANUFACTURE OR SALE OF APPARATUS WITHOUT PERMISSION. COPYRIGHT @ 2013 EDGETECH INC.
REVISIONS
REV DESCRIPTION DATE APPROVED
A Initial Release
Ethernet 4 x 2
Trig A 1 Blu 1 Trig A
TrGnd 2 Blu/Wht 2 Trig GND/1 PPS GND
Ylw1
RS232 GND 3 Ylw2 3 RS232 GND
Tx2 4 Brn1 4 Tx2
Rx2 5 Brn2 5 Rx2
Tx1 6 Red1 6 Tx1
Rx1 7 Red2 7 Rx1
Org1
Subconn 16F
Rx3 8 Org2 8 Rx3
1PPS 9 Blu1 9 1PPS
Blu2
TX3 10 Grn1 10 TX3
Grn2
0V 11 Wht1 11 0V
Wht2
Subconn 16M
Dn- 12 Wh/Org 12 Dn-
Dn+ 13 Org 13 Dn+
Up- 14 Brn/Wht 14 Up-
Up+ 15 Brn 15 Up+
+VDC 16 Blk1 16 +VDC
Blk2
Gry1
Gry2
Label
(P/N: 0009833)
Wet Mate Connector SubConn 16 pin FEMALE MCIL16F
DLSA-F
0013357 Rev A
DLSA-F
Wet Mate Connector, SubConn 16 pin MALE MCIL16M
(4 Twisted Pairs #24 AWG Cat5)
(18 #22 AWG Single Conductors)
10 Meters +/-0.1m
Cable ET Supplied FALMAT
FMXCAT52218K12
(P/N: 0010379)
APPROVALS DATE
DRAWN: PO 6/6/2013
CHECKED: DWF 6/6/2013
ENG:
ISSUED
SYSTEM 4605
EdgeTech
1141 Holland Drive, Suite 1
Boca Raton, FL 33487
Tel: (561) 995-7767 / Fax: 995-7781
Email: FullSpectrum@EdgeTech.com
ASSY TOP CABLE 4605 TOWFISH 16 PIN SUBCONN 10 METERS
CAD/FILE NAME
DRAWING NO. 0013357
REV A
SCALE page 1 of 1

Figure C-5: 6205 Wiring Diagram



Figure C-6: 6205-P Portable Topside Interface Box

The 6205 Arrays have been color coded based on their operating frequency. The color code is shown and described below:



Color Code:

Blue = 230/550SS– 230 Bathy
Red = 230/550SS – 550 Bathy
Yellow = 550/850SS – 550 Bathy
Green = 550/1600SS – 550 Bathy

Figure C-7: Array Color Codes